Level instrumentation for gas process equipment

DELIVERY REGION

Middle East

PERIOD

2025



Photograph from the project.

KEY PARAMETERS

12 main instruments

10 level gauges + 2 transmitters

Indicative financial band

EUR 10,000-50,000

Invoiced instrument package; excluding VAT

Partial instrument supply

Supply of twelve main level instruments for gas process equipment. The lot combined ten L21 level gauges and two displacer transmitters; selected versions included thermal insulation or an additional local indicator. Spare parts complemented the instrument supply.

SCOPE OF WORK

- 10 L21 level gauges, SS316 and SS321 materials
- 2 displacer transmitters with Fisher DLC3010 electronics
- Selected positions with insulation and an ABB JDF200 indicator

EMKO project portfolio. Supplier at the time of delivery: EMKO HOLDING s.r.o.