REFERENCE SHEET

PROJECT 1171

Rails for raking machines

PROJECT LOCATION

Pardubice, Czechia

PERIOD

June 2026



Rail and guide detail of the raking machine from the project documentation.

KEY PARAMETERS

2 rails

5.8 m per rail

11.6 m total

Indicative financial band

up to CZK 100,000

Invoiced rail manufacture and supply; excluding VAT

Custom manufacture and supply

Manufacture and supply of two rails for reclaiming machines at a plant in Pardubice. Each part was 5,800 mm long with mounting holes to the drawing, giving a total supplied length of 11.6 m.

SCOPE OF WORK

- Two rails, each 5,800 mm long
- 11.6 m total supplied length
- Mounting holes manufactured to the drawing
- U 50 channel and S235JR steel specified in the offer

Supplier: EMKO PROJECT s.r.o.