Refurbishment of formalin process heat exchangers

EXPORT PROJECT REGION

Middle East

PERIOD

2020-2021



Refurbished exchangers after protective coating work, prepared in the workshop yard.

KEY PARAMETERS

17 exchangers in the refurbishment report

8 heaters and 7 pressure relief valves

Piping stage: 11.12 t net

Refurbishment and partial dispatch stages

Staged refurbishment of selected formalin process equipment for an export project. Documented work covers 17 shell-and-tube heat exchangers, repairs and checks of electric heaters, servicing of pressure relief valves and preparation of piping assemblies for transport.

SCOPE OF WORK

- Refurbishment of 17 shell-and-tube exchangers; pressure tests at 10 barg / 15 minutes
- Repairs and checks of 8 electric heaters; service of 7 pressure relief valves
- Replacement seals, protective coating and preparation for transport
- Piping stage: DN 40-350, 11.12 t net in three packing records

Historical project portfolio; the commercial records identify the supplier as MIS GROUP s.r.o., company ID 04624688.