EMKO PROJECT

REFERENCE SHEET

PROJECT 731

Reactor tray assembly refurbishment

PROJECT LOCATION

Šaľa, Slovakia

PERIOD

2025



Reactor tray internals prepared for dispatch in September 2025.

KEY PARAMETERS

11 reactor trays

22 tray halves

Grade 1.4466 steel

Indicative financial band

EUR 50,000-100,000

Invoiced reactor-internals supply; excluding VAT

Assembly refurbishment

Supply of components to refurbish eleven reactor trays at a chemical plant in Šaľa. The 1.4466 steel internals comprised 22 tray halves together with sealing, support and connection components.

SCOPE OF WORK

- 11 trays comprising 22 halves
- Grade 1.4466 specified in the manufacturing and delivery records
- 363 components listed in the final packing list
- Structural parts supplied for installation inside an existing reactor

EMKO project portfolio. Supplier at the time of delivery: EMKO HOLDING s.r.o.