EMKO PROJECT

REFERENCE SHEET

PROJECT 1126

Shutdown maintenance of sodium nitrate production

LOCATION

Pardubice, Czechia

PERIOD

2026



Photograph from the project.

KEY PARAMETERS

4 fans in the scope

2 evaporators in the scope

13 service items

Indicative financial band

CZK 100,000-500,000

Invoiced shutdown work; excluding VAT

Shutdown maintenance and repairs

Shutdown maintenance at a chemical plant in Pardubice combined work on fans, evaporators, pumps and associated pipework. The site diary records dismantling, repairs, resealing and reassembly; the work area was handed over on 3 July 2026.

SCOPE OF WORK

- Four fans and two evaporators in the service schedule
- Pumps with cooling tanks and a Venturi scrubber
- Separation station with screw, decomposition vat and pipework
- Mechanical repairs, bearing replacement and joint resealing

Supplier: EMKO PROJECT s.r.o.